

**Volume-II**

**NATIONAL AGRI-FOOD BIOTECHNOLOGY INSTITUTE (NABI)**

(Department of Biotechnology,  
Ministry of Science and Technology, Govt. of India)  
C-127, Industrial Area, Phage 8, SAS Nagar, Mohali, Punjab

**FINANCIAL BID DOCUMENT**



**PROVIDING & FIXING OF AUDITORIUM CARPET AT NABI-CIAB, MAIN  
CAMPUS, SECTOR-81, MOHALI**

# **TECHNICAL SPECIFICATIONS**

## **1.0 STANDARD SPECIFICATIONS TO BE FOLLOWED**

The work should be executed as per following CPWD specification and also the specification laid in tender document. In case, above specifications are not available for certain item, then the material should conform to ISI and BIS standards.

### **1.1 Civil Engineering Works**

CPWD Specification 2009 Vol. I & II along with latest correction slips. These Specifications have replaced CPWD Specifications 1996 along with Correction Slips issued on them. These Specifications cover all types of Works. The specifications are available as a printed document issued by CPWD and also in soft copy PDF Format in CPWD website.

#### **A. Auditorium Floor Carpet**

Providing and fixing anti-flammability, anti static, moth proofed carpet (Make Rossetta, Spartan series model no 2822) made out strudon PP BCF graphic loop pile of pile height of minimum 4 mm, total height of 6mm . The minimum pile and total weight of carpet shall be 675 gsm & 1325 gsm . The carpet shall be fixed with suitable benzene free , non -hazardous synthetic adhesive (Pidilite SR 998, BASF, Sikka etc) on existing stepped cement concrete floor , complete as per directions of Engineer- in -charge. The sample is available in this office, which may be seen before submission of bids by bidders. The cost of adhesive, fixing, labour, profits, taxes, wastage etc should be included in the quote.

#### **B. Aluminium Work:-**

The work shall be executed as per CPWD, NIT specifications. The aluminium strips shall be fixed with suitable fasteners/screws etc. The sample to be provided before mass execution at site.

**NAME OF WORK:** - PROVIDING & FIXING OF AUDITORIUM CARPET AT NABI-CIAB,  
MAIN CAMPUS, SECTOR-81, MOHALI

**ABSTRACT SHEET**

<b>S.NO</b>	<b>PARTICULARS</b>	<b>AMOUNT (In INR)</b>
1	ESTIMATED VALUE OF WORK	Rs 13, 11, 828/-
2	PERCENTAGE (% AGE) QUOTE PLUS/MINUS (+/ -) BY BIDDER ON ESTIMATED AMOUNT (IN FIGURES)	
3	PERCENTAGE (% AGE) QUOTE PLUS/MINUS (+/ -) BY BIDDER ON ESTIMATED AMOUNT (IN WORDS)	
4	NET AMOUNT AFTER UN-CONDITIONAL PERCENTAGE REBATE OR QUOTE ABOVE ESTIMATED VALUE ((IN FIGURES)	
5	NET AMOUNT AFTER UN-CONDITIONAL PERCENTAGE REBATE OR QUOTE ABOVE ESTIMATED VALUE ((IN WORDS)	

Stamp & Signatures of bidder

**B.O.Q FOR PROVIDING & FIXING OF AUDITORIUM CARPET AT NABI-CIAB,  
MAIN CAMPUS, SECTOR-81, MOHALI**

S. No	Description	Unit	QTY	Rate	Amount
1/NS	Providing and fixing anti-flammability, anti static, moth proofed carpet (Make Rossetta, Spartan series model no 2822) made out strudon PP BCF graphic loop pile of pile height of minimum 4 mm, total height of 6mm . The minimum pile and total weight of carpet shall be 675 gsm & 1325 gsm . The carpet shall be fixed with suitable benzene free , non - hazardous synthetic adhesive (Pidilite SR 998, BASF, Sikka etc) on existing stepped cement concrete floor , complete as per directions of Engineer- in -charge. The sample is available in this office, which may be seen before submission of bids by bidders.	SQMTRS	561.9425	1969.757	1106890.012
2/21. 1.1.2	Providing and fixing aluminium work for fixing of carpet at steps built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc.				
	Powder coated aluminium (minimum thickness of powder coating 50 micron) in step nozing	KG	533.0	384.5	204938.5
	<b>TOTAL AMOUNT INCLUSIVE OF TAXES</b>				<b>1311828.51</b>
				<b>SAY Rs 13,11,828/-</b>	

**TOTAL ESTIMATED AMOUNT INCLUSIVE OF TAXES, PROFITS, LABOUR ETC = Rs 13, 11,828/-**

NOTE: - Payment shall be released item wise based on actual measurement examined at site by Engineer- In- Charge.

Signature/Stamp of Bidder